BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division

Schedule-B

NAME OF THE WORK: Providing covering slab to drainage KK Road at T.Dasarahalli in ward no. 15 Dasarahalli sub division

Sl. No	Description of work	Unit	Qty	Rate Quoted by Sri. N.Thippeswamy	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Dismantling of Existing Structures like culverts, Bridges, retaining walls and other structure compressing of masonary, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary sorting the dismanteled meterial, disposal of unserviseble material and stacking the serviceble material with all lifts complete as per specifications. (Page No:136, itNo: 18.19) 2016-17	**Cum**	52.38	450.0	Rupees Four Hundred Fifty Only
2	KSRRB 300 - Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3 (P.142/I.19.1 PW, P & IWTD -SR 2016-17)	Cum	43.47	250.0	Rupees Two Hundred Fifty Only
3	KSRRB M2100-10. Plain cement concrete M-10 with OPC cement at 220kg with crushed 40mm down size graded granite metal course aggregate @0.84 CUM and fine agreegate @ 0.6 CM in Foundation mechanically mixed placced in foundation and compacted by vibration including curing for 14 days complete as per specifications. MORTH Specification No. 2100. Page No. 218/ Item No. 27.18/ PWD SR 2016-17	Cum	17.39	5200.0	Rupees Five Thousand Two Hundred Only
4	KSRB M2200-5.9 Design Mix M20 with OPC cement @ 320kgs with 20mm & down size graded granite metal course agreegate @ 0.69 CM an Fine agregated 0.46 cm with super plaster @ 3ltrs confirming to IS 9103-1999 Reaffirmed -2008 i.) Upto 5m height Page No. 223/ Item No. 28.7.9/ PWD SR 2016-17	Cum	67.91	5800.0	Rupees Five Thousand Eight Hundred Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division

5	KSRB M-2200- TMT/MS bar Reinforcement KSRRB M2200-6 Supplying, fitting and placing TMT bar reinforcement in Sub-structure complete as per drawing and technical specifications complete as per specifications. MORTH specification No. 1600 & 2200. Page No. 225/ Item No. 28.8/ PWD SR 2016-17 TMT Bars FE 550	Tonne	2.44	53000.0	Rupees Fifty Three Thousand Only
6	Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials.	Cum	436.50	1450.0	Rupees One Thousand Four Hundred Fifty Only
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Page No. 150 Item No. 17.1 PWD SR 2016-17	Cum	43.47	150.0	Rupees One Hundred Fifty Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Executive Engineer
Dasarahalli Division